

EMC.D-VXR-DY-23.v2024-12-25.q116

Exam Code:	D-VXR-DY-23
Exam Name:	Dell VxRail Deploy 2023
Certification Provider:	EMC
Free Question Number:	116
Version:	v2024-12-25
# of views:	898
# of Questions views:	1160
https://www.freepdfdumps.com/EMC.D-VXR-DY-23.v2024-12-25.q116.html	

NEW QUESTION: 1

You have just upgraded a VxRail Cluster from version 4.5.x to version 4.7.x. You need to ensure that new VxRail 4.7.x nodes will be discovered to enable Cluster expansion. The customer does not want to make any changes to the existing ToR switch infrastructure.

What action is necessary to ensure discovery of the new nodes?

- A.** In vCenter, create a new distributed portgroup Private Management Network with VLAN ID 3939
- B.** Change the Management Network VLAN ID on each new node to match the management VLAN ID of the existing Cluster Restart loudmouth
- C.** Change the Private Management Network VLAN ID on each new node to match the management VLAN ID of the existing Cluster Restart loudmouth
- D.** In vCenter, set the VLAN ID of the VxRail Management distributed portgroup to 3939

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 2

Which series of VxRail nodes supports either Intel or AMD processors and either hybrid or All-Flash storage?

- A.** D Series
- B.** G Series
- C.** V Series
- D.** E Series

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 3

What is the correct sequence of steps to perform a RASR Factory Reset using an SD card?

Boot the node from the internal SD card	Step 1
Acknowledge the Warning and Caution messages, then type "Disconnected" to proceed	Step 2
Access iDRAC and launch virtual console to the VxRail node	Step 3
Quit the RASR menu and reboot the system	Step 4
Select F – Factory Reset in the RASR Menu	Step 5

Answer:

Boot the node from the internal SD card	Access iDRAC and launch virtual console to the VxRail node
Acknowledge the Warning and Caution messages, then type "Disconnected" to proceed	Boot the node from the internal SD card
Access iDRAC and launch virtual console to the VxRail node	Select F – Factory Reset in the RASR Menu
Quit the RASR menu and reboot the system	Acknowledge the Warning and Caution messages, then type "Disconnected" to proceed
Select F – Factory Reset in the RASR Menu	Quit the RASR menu and reboot the system

NEW QUESTION: 4

An implementation engineer is tasked with expanding an 8-node VxRail E560 cluster with an S570 node. The cluster has been configured with 1 GbE networking.

Which two should be considered when planning to expand the cluster? (Select 2)

- A. All nodes in the cluster must be the identical series
- B. E Series nodes require more capacity before expansion
- C. Node limit has been reached on the cluster
- D. AMD and Intel based nodes cannot be mixed

Answer: (SHOW ANSWER)

NEW QUESTION: 5

What code is returned when a VxRail API request is executed successfully?

- A. 200
- B. 400
- C. 500
- D. 207

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 6

What is required to enable vSAN encryption on a VxRail cluster?

- A. Internal vCenter Server
External Key Management Server
- B. Internal vCenter Server
Internal Key Management Server
- C. All-Flash system
External Key Management Server
- D. External vCenter Server
External Key Management Server

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 7

A VxRail cluster is being deployed in a DMZ environment.

What is the recommended deployment option?

- A. Internal vCenter Server with internal DNS
- B. External vCenter Server with customer-supplied VDS
- C. External vCenter Server with VxRail-deployed VDS
- D. Internal vCenter Server with external DNS

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 8

Which step must occur prior to deploying a 2 node VxRail Cluster?

- A. Witness Traffic Separation configured
- B. All ports connected to ToR switch
- C. Witness deployed and running
- D. Cluster object created in vCenter

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 9

A systems engineer notices that a VxRail host that previously appeared in a cluster within vCenter is now disconnected and is not responding. The VMs that were running on that host have been recovered on other available hosts.

What initial action needs to be done to resolve the issue?

- A. Review event logs for errors and perform root cause analysis
- B. Generate the appropriate SolVe procedure and follow it
- C. Use iDRAC to check the physical state of the nodes
- D. Apply the latest updates on the host

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 10

A failure occurs during the deployment of a VxRail cluster. You need to look through the marvin.log file to see what could be causing the error.

Where is this file located?

- A. var/log/vmware/marvin/tomcat/logs
- B. var/log/mystic
- C. var/log/vmware
- D. var/log/vmware/marvin

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 11

Which proactive vSAN tests are built in vCenter?

- A. Network performance and firewall port simulation
- B. VM creation and network performance
- C. VM creation and data utilization simulation
- D. Firewall port and data utilization simulation

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 12

An infrastructure system audit will begin in two weeks. All data center devices will be checked to ensure they contain the installed patches and configurations. A system engineer will update the VxRail hosts with the latest patches and remediate security vulnerabilities.

What troubleshooting resource can a user receive from Dell and use proactively to help perform the remediation tasks?

- A. KB articles
- B. Log files
- C. Advisories
- D. SolVe Online

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 13

A systems engineer is tasked to configure a VxRail cluster and notices that the VxRail Deployment Wizard fails to launch. The engineer discovers that the software is corrupted.

What should the engineer do to address the issue?

- A. Use the VMware Host Client and iDRAC to access the nodes for troubleshooting
- B. Return the nodes to the original build state
- C. Check vCenter and troubleshoot the build failure
- D. Verify that the JSON file is not corrupted and has all the required values

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 14

What is configured by default during the initial deployment of a VxRail cluster with All-Flash nodes?

- A. vSAN Performance Service
- B. AID-1 vSAN storage policy
- C. vSAN Deduplication and compression
- D. RAID-5 vSAN storage policy

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 15

Which two vSAN licenses include entitlement for VMware HCI Mesh? (Select 2)

- A. Standard
- B. Advanced
- C. Enterprise Plus
- D. Enterprise

Answer: C,D ([LEAVE A REPLY](#))

NEW QUESTION: 16

A company has multiple VxRail systems installed at geographically dispersed data centers. They want to upgrade all their VxRail systems to the latest release. Before the upgrade, they want an inventory report of all the VxRail systems which shows the current health status and versions of all installed VxRail components.

What should be used to meet these requirements?

- A. itrend
Live Optics
- B. Mitrend
VxRail Log insight
- C. VxRail Plugin for vCenter Server
VxRail API
- D. VxRail Plugin for vCenter Server
DRM Services

Answer: B ([LEAVE A REPLY](#))

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)

NEW QUESTION: 17

In addition to the VxRail YouTube video, links to what resources should the SE send to the customer, according to the VxRail PEQ Engagement Details worksheet?

- A. VxRail vCenter Server Planning Guide Network Validation Tool
- B. VxRail QuickStart Guide VxRail Network Guide
- C. VxRail QuickStart Guide Network Validation Tool
- D. VxRail vCenter Server Planning Guide VxRail Network Guide

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 18

A company has a two chassis G Series cluster and wants to change the setup. This will require a reset of the chassis.

What is the correct procedure?

- A. Reset the secondary chassis first, followed by the primary chassis, through the reset script.
- B. Reset the primary chassis first, followed by the secondary chassis, through the reset script.
- C. Reset both chassis simultaneously through the reset script
- D. Reset both chassis simultaneously with the mobile build server

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 19

Which VxRail models support the installation of rack rails with a cable management arm?

- A. E, G, P, and S Series
- B. E, P, S, and V Series
- C. D, G, P, and S Series
- D. D, E, S, and V Series

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 20

How must node ports on Dell EMC ToR switches be configured when the Spanning Tree Protocol is enabled in an environment?

- A. In Forwarding status
- B. In Port-Channel mode
- C. As edge ports

D. As access ports

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 21

What is the Dell EMC recommendation for VxRail Management VLANs?

- A. Configure the VLAN ID with a default of 1
- B. Use untagged traffic on the Native VLAN for the Public Management network
- C. Configure the VLAN ID with a default of 3940
- D. Use tagged traffic on the Native VLAN for the Public Management network

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 22

From what environment must a network administrator run VxRail network validation?

- A. Same subnet as VxRail Management Network
- B. Top of Rack switches
- C. Windows PowerShell command prompt
- D. VxRail Deployment Wizard

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 23

When using VxRail Manager, what is the source of information that can help validate good VxRail system post-deployment status?

- A. MARVIN-Virtual-SAN-Cluster > Monitor > Virtual SAN > Health
- B. MARVIN-Virtual-SAN-Cluster > Manage > Health and Performance
- C. Last Heartbeat, Last Configuration Sent, Network Environment Settings, Cluster Monitor
- D. System Diagnostic, Events, Health Logical View, Health Physical View, Log Bundle

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 24

What is the maximum number of supported nodes in a VxRail Stretch Cluster?

- A. 16
- B. 64
- C. 30
- D. 32

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 25

What action is required to enable VxRail Manager the ability to update system software and browse VxRail KB articles?

- A. Configure Proxy settings
- B. Enable Secure Remote Support (SRS)

- C. Set the appliance status to 'Installed' in the Dell EMC Install database
- D. Set the Username and Password for the Support Account

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 26

What step is a best practice in the deployment process of a VxRail Appliance with an External vCenter server?

- A. Create VxRail Configuration user in SSO with no role assigned
- B. Create VxRail Management user in SSO with administrative privileges
- C. SSH to the default IP address of the VxRail Manager VM to set the required IP address
- D. Connect to DCUI to set vLAN tagging on ESXi hosts

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 27

During the activation of Internal SRS, the implementation engineer receives a message that the deployment has failed What is a possible cause?

- A. Site ID mismatch between the IB database and the SRS Wizard
- B. SRS VE Gateway on the same subnet as the VxRail Manager
- C. Witness Gateway not configured following Dell best practices
- D. VxRail status already set to installed' in IB database

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 28

What is the maximum number of VxRail 4.7.x Clusters you can create with three G Series nodes and five E Series nodes?

- A. 1
- B. 3
- C. 2
- D. 4

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 29

Which service determines the primary node after powering on the VxRail nodes during the deployment of a VxRail cluster?

- A. Election
- B. Mystic
- C. Marvin
- D. Loudmouth

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 30

You are performing a troubleshooting steps on a 4 node VxRail cluster. The cluster uses Erasure Coding for all VMs. When you attempt to put a node into maintenance mode using the recommended vSAN data migration policy, the operation fails.

What could be done to successfully put the node into maintenance mode?

- A. Cold migrate the VMs off the node
- B. Use the 'No Data Migration' option
- C. Use the 'Full Data Migration' option
- D. Storage vMotion the VMs off the node

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 31

You want to deploy VxRail, leveraging your existing VMware SSO domain.

What is the recommended method?

- A. Deploy Embedded vCenter with Embedded PSC
- B. Configure Embedded vCenter in Enhanced Linked Mode
- C. Deploy External vCenter with no PSC
- D. Deploy to an External vCenter

Answer: ([SHOW ANSWER](#)**)**

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)

NEW QUESTION: 32

How many cables are required to install a 4 node VxRail Model G410 cluster with 1 GbE into a rack?

- A. 20 CAT6 network cables
- B. 4 CAT6 and 32 SFP+ connectors, and 16 fiber cables
- C. 4 CAT6 and 8 Twinax network cables
- D. 4 CAT6 and 16 Twinax network cables

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 33

What is the correct CLI command to collect only the VxRail Manager logs?

- A. vm-supportsh -c
- B. generateLogBundle py -v

- C. vc-support sh -v
 - D. generateFullBundle.py -c
- Answer: D ([LEAVE A REPLY](#))**

NEW QUESTION: 34

A company wants to deploy VxRail on V Series nodes as a proof-of-concept (POC). Only one Top of Rack (ToR) switch has been provided for the POC.

What is the Dell EMC best practice recommendation in this situation?

- A. Connect each host NIC to a port on a different switch packet buffer bank on the ToR switch. Balance the ports across two packet buffer banks.
- B. Connect the first host NIC to the TOR switch. Daisy chain the second NIC between hosts.
- C. Connect the first host NIC to the ToR switch. Leave the second host NIC un-cabled.
- D. Inform the company that the POC cannot proceed without a second ToR switch.

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 35

A VxRail cluster is being deployed with an existing vCenter Server.

Which role needs to be assigned to the new VxRail Management User account within vCenter Server?

- A. Trusted Infrastructure Administrator role
- B. No role needs to be assigned
- C. Read-only role
- D. Administrator role

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 36

What is a benefit when using VxRail-Managed vCenter?

- A. Additional virtual distributed switch options.
- B. Enhanced security requirements.
- C. Ease of VM Migration across multiple clusters.
- D. Ease of operation for lifecycle management.

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 37

What is a characteristic of the VxRail S Series node?

- A. Form factor of 1U1N
- B. Dense Flash disks
- C. Form factor of 2U4N
- D. Large form factor drives

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 38

For which typical activity would the No data migration setting be used when placing a VxRail host into maintenance mode?

- A. Permanently removing host from cluster
- B. Relocating host to remote data center
- C. Temporary maintenance
- D. Shutting down an entire cluster

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 39

You have been asked to deploy a single, 4 node VxRail cluster for company. They would like to migrate from their existing vSphere 6.5 environment. They have also asked that vCenter Enhanced linked-mode be supported.

Based on best practice, what is the recommended deployment model?

- A. Deploy Internal vCenter with Embedded PSC
- B. Use existing vCenter 6.5 with Embedded PSC
- C. Deploy Internal vCenter with External PSC
- D. Use existing vCenter 6.5 with External PSC

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 40

Match each VxRail API Method to its respective VxRail Manager function.

A. DELETE - Edit or update an existing resource

POST - Retrieve a resource

PUT - Remove a resource

GET - Create a resource

B. DELETE - Remove a resource

POST - Retrieve a resource

PUT - Edit or update an existing resource

GET - Create a resource

C. DELETE - Remove a resource

POST - Create a resource

PUT - Edit or update an existing resource

GET - Retrieve a resource

D. DELETE - Create a resource

POST - Remove a resource

PUT - Edit or update an existing resource

GET - Retrieve a resource

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 41

While preparing for an onsite visit for an installation of a VxRail cluster, a Dell installation engineer is unable to generate a Restricted Procedure in the SolVe Online portal.

What is the cause?

- A. The SolVe Online portal is viewed as a customer
- B. SolVe Online portal has not been updated with the latest procedures
- C. The engineer has not been approved for VxRail procedures in the SolVe Online portal

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 42

Which command is used to restart the Loudmouth process on an ESXi node?

- A. /etc/int.d/loudmouth restart
- B. systemctl restart loudmouth
- C. /usr/libAmiware/loudmouth/bin/loudmouthd restart
- D. systemctl restart vmware-loudmouth

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 43

You require a service tag for a VxRail service request. Where could you find this?

- A. Cluster level physical view
- B. Appliance level physical view
- C. VxRail Manager BIOS
- D. Secure Remote Services device list

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 44

What is a permissible configuration when performing a cluster expansion?

- A. New nodes should be on a different subnet prior to deployment.
- B. Mixing of all-flash and all-NVMe nodes in a cluster.
- C. Use 25 GbE for VMNetwork, 10 GbE for VSAN, and 1 GbE for Management.
- D. Mixing of AMD-based nodes and Intel-based nodes.

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 45

An implementation engineer is deploying a new VxRail cluster.

What should they confirm before installing the hardware?

- A. At least 24 in (61 cm) of clearance must exist in front of and behind the cabinet
- B. Redundant power zones exist with adequate power cables
- C. Service laptop is on the same IP network as the iDRACs
- D. Power distribution supports only the power rating of a single node

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 46

A company is in the process of configuring their Top of Rack (ToR) switches as a single rack that replicates to a secondary data center with vSphere Replication.

What is a consideration for this configuration?

- A. IPv6 and IPv4 multi-cast should span the entire network in each data center
- B. IPv6 and IPv4 multi-cast should be layer-3 routed between data centers
- C. IPv6 and IPv4 multi-cast traffic does not need to leave the ToR switches
- D. IPv6 and IPv4 multi-cast traffic should span layer-2 between data centers

Answer: ([SHOW ANSWER](#))

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF**

Special Discount: Freepdfdumps)

NEW QUESTION: 47

A VxRail running version 4.7.100 has been deployed in a SmartFabric configuration. The customer needs to set up management of their networking for the Cluster.

What steps are required to complete this task?

- A. Download, install the OME plug-in, and run the Python script
- B. Download and install OME plug-in
- C. Download the OMNI plug-in, enable vCenter, and run the Python script
- D. Download and install the OMNI plug-in

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 48

What should you use to create the customer deliverable documentation of a VxRail deployment?

- A. As-Built Configuration Generator
- B. VxRail Manager
- C. SolVe Online
- D. E-Lab Advisor

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 49

What is a requirement for the vSAN Data-at-Rest Encryption?

- A. External Key Management Server
- B. External customer provided vCenter

- C. All-Flash or All-NVMe VxRail
- D. VxRail with at least 3 nodes

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 50

How can an administrator manually verify DNS records for a VxRail implementation?

- A. ping
- B. ipconfig/all
- C. ping -a
- D. nslookup

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 51

What network protocol is required for a VxRail Management VLAN?

- A. IPv6 Unicast
- B. IPv4 Unicast
- C. IPv6 Multicast
- D. IPv4 Multicast

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 52

A company needs to enable vSphere GPU capabilities on their VxRail cluster. To do so, they need to purchase a specific entitlement.

What licensing satisfies this requirement?

- A. vSphere Standard
- B. vSAN Advanced Edition
- C. vSphere Enterprise Plus
- D. vSAN Enterprise Plus Edition

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 53

The vCenter managing a VxRail cluster must be able to support both Enhanced Linked Mode and vSAN Encryption.

What is the correct configuration to satisfy this requirement?

- A. Embedded vCenter External PSC
- B. External vCenter Embedded PSC
- C. Embedded vCenter Embedded PSC
- D. External vCenter External PSC

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 54

What is the minimum number of VxRail hosts required if FTT = 1 and FTM is set to Erasure Coding?

- A. 5
- B. 3
- C. 6
- D. 4

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 55

You are asked to cable up a VxRail G Series cluster to a redundant pair of 1/10G switches. What is the cabling best practice for this configuration?

- A. Cable ports 1 and 2 to one switch. Cable ports 3 and 4 to the other switch.
- B. Cable ports 1 and 2 to one switch. Cable ports 3 and 4 to the other switch. Cable BMC from node 1 and 2 to one switch. Cable BMC from node 3 and 4 to the other switch.
- C. Cable ports 1 and 3 to one switch. Cable ports 2 and 4 to the other switch.
- D. Cable ports 1 and 3 to one switch. Cable ports 2 and 4 to the other switch. Cable BMC from node 1 and 3 to one switch. Cable BMC from node 2 and 4 to the

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 56

An existing Dell EMC customer wants to deploy a new VxRail cluster on premise. Each node of the new cluster will be configured with a single disk group containing one 1.6 TB Flash drive for the capacity tier. The customer plans on using mirroring and needs to have at least 2 TB of usable capacity in the vSAN datastore.

What is the minimum number of VxRail nodes required?

- A. 3
- B. 2
- C. 4
- D. 5

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 57

During a VxRail deployment validation check it is discovered that the Top of Rack (ToR) switches have Spanning Tree Protocol enabled.

What should be done before the implementation can proceed?

- A. Confirm that ToR switch ports connected to VxRail nodes are configured to get into "forwarding" mode quickly.
- B. Confirm that ToR switch ports connected to VxRail nodes have fabric-trunk enabled.
- C. Confirm that isolated VLANs exist on the ToR switches for each of the VxRail networks.
- D. Disable STP on the ToR switches

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 58

Which items are validated during the NVT test?

- A. DNS and WINS
- B. DNS and NTP
- C. Latency and NTP
- D. Bandwidth and STP

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 59

What is the default IP address of the VxRail Manager?

- A. 192.168.10.200
- B. 192.168.10.16
- C. 192.168.1.200
- D. 192.168.1.16

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 60

What categories can be validated by the VxRail NVT?

- A. Network Services, Upstream Switches, and VxRail Nodes
- B. ToR Switches, Upstream Switches, and VxRail Nodes
- C. Network Services, ToR Switches, and VxRail Nodes
- D. Network Services, ToR Switches, and Upstream Switches

Answer: ([SHOW ANSWER](#)**)**

NEW QUESTION: 61

What is the purpose of the As-Built Configuration Generator?

- A. Create the customer deliverable documentation of the Dell EMC product/solution implementation
- B. Keep a record of all spare nodes, not yet added to a VxRail Cluster
- C. Capture and generate the installation workflow for review in the event of a failed deployment
- D. Provide advanced control grouping for Stretched Clusters

Answer: ([SHOW ANSWER](#)**)**

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here:

Special Discount: **Freepdfdumps**)

NEW QUESTION: 62

What network setting is the optional configuration on the port group for a customer-supplied VDS before the VxRail cluster is deployed?

- A. Enable and configure NIOC
- B. Assign NIC uplinks
- C. Enable NIC teaming and failover
- D. Configure NIC teaming and failover

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 63

A VxRail E560F model was delivered six months ago and is now scheduled to be installed with the target code.

What is the correct order of steps to complete this task?

Create RASRUSB and boot from USB stick	Step 1
Perform Factory Reset and boot from BOSS	Step 2
Boot the node from mounted RASR ISO	Step 3
Install DUPs and boot from SD	Step 4
Perform RASR Reset and boot from SD	Step 5

Answer:

Create RASRUSB and boot from USB stick	Perform RASR Reset and boot from SD
Perform Factory Reset and boot from BOSS	Create RASRUSB and boot from USB stick
Boot the node from mounted RASR ISO	Perform Factory Reset and boot from BOSS
Install DUPs and boot from SD	Boot the node from mounted RASR ISO
Perform RASR Reset and boot from SD	Install DUPs and boot from SD

NEW QUESTION: 64

Which steps need to be taken to perform a file based restore of VxRail Manager?

- A. Restore the latest cloned copy of the VxRail Manager VM from the BOSS drives on nodes 1 and 2.

B. Deploy a new VxRail Manager VM and rediscover the cluster environment executing the vxm_cluster_discovery.py script.

C. Deploy a new VxRail Manager VM and restore the configuration from backup with the vxm_backup_restore.py script.

D. Restore the initial clone of the VxRail Manager VM and it will update itself to the latest status.

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 65

An implementation engineer is deploying a VxRail cluster at a secure site that does not allow access to the external DNS server.

How should the VxRail be deployed?

A. With customer provided external vCenter and internal DNS

B. VxRail cannot be deployed in this environment

C. With internal vCenter and hostfiles for name resolution

D. With internal vCenter and internal DNS

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 66

A newly installed VxRail system appears to have poor vSAN performance for all VMs on the cluster.

What can be used to identify the issue?

A. esxtop with x view

B. resxtop with d view

C. resxtop with s view

D. esxtop with v view

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 67

Which vSAN feature requires an All-Flash cluster?

A. Data-at-Rest Encryption

B. Deduplication and compression

C. Storage Policy Based Management

D. Data-in-Transit Encryption

Answer: ([SHOW ANSWER](#)**)**

NEW QUESTION: 68

A VxRail cluster 4.7.xxx environment is managed by the internal vCenter Server. An implementation engineer plans to deploy a new VxRail cluster using the existing vCenter Server instance, then use the customer-supplied VDS to manage both VxRail clusters.

What must be done?

A. Migrate the internal vCenter Server to an external vCenter Server, then merge the PSC

- B. Upgrade the internal vCenter Server to version 7.0
- C. Upgrade the VxRail version from 4.7.xxx to 7.0.000
- D. Migrate the internal vCenter Server to an external vCenter Server, then upgrade the VxRail 4.7.xxx to 7.0.100

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 69

A VxRail D560 cluster was delivered six months ago and now needs to be prepared for installation with the target code.

What is the correct method to complete the task?

- A. Boot into RASR USB and perform a RASR Reset
- B. Boot into SD card and perform a Factory Reset
- C. Boot into RASR ISO and perform a RASR Reset
- D. Boot into RASR ISO and perform a Factory Reset

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 70

What can be used to determine whether hardware faults exist on a VxRail prior to its deployment?

- A. VxRail NVT
- B. VxRail Pre-validation
- C. iDRAC
- D. PEQ

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 71

What is a valid 2-node VxRail cluster configuration?

- A. 2x 1 GbE and 2x 10 GbE in a switch configuration and internal vCenter
- B. 2x 1 GbE and 2x 10 GbE in a direct-connect configuration and external vCenter
- C. 2x 10 GbE and 2x 25 GbE in a direct-connect configuration and internal vCenter
- D. 2x 10 GbE and 2x 25 GbE in a switch configuration and external vCenter

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 72

A 4-node VxRail Model E560F solution with an embedded vCenter and Log Insight is planned for deployment.

Prior to deployment, DNS records must be created for which hosts?

- A. vCenter Server, ESXi hosts, VxRail Manager, and Log Insight
- B. vCenter Server, first ESXi host, VxRail Manager, and iDRAC
- C. vCenter Server, ESXi hosts, VxRail Manager, and iDRAC
- D. DNS records are automatically created during VxRail deployment

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 73

Which two files are used to automate VxRail deployment and validate the network configuration?

A. Appliance JSON file

PEQ data file

B. VxRail Configuration Portal

PEQ data file

C. VxRail Test Plan

SPEQ

D. Appliance JSON file

SPEQ

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 74

A VxRail solution will be deployed with the embedded vCenter and an external DNS. At a minimum, for which components must DNS records be created?

A. vCenter Server, ESXi hosts, and VxRail Manager

B. vCenter Server Platform Services Controller, and iDRAC

C. ESXi Hosts, VxRail Manager and iDRAC

D. vCenter Server Platform Services Controller, and VxRail Manager

Answer: **A** ([LEAVE A REPLY](#))

NEW QUESTION: 75

What is the remote management option for G Series VxRail nodes?

A. IPMI/BMC

B. RMM

C. iLO

D. iDRAC

Answer: **A** ([LEAVE A REPLY](#))

NEW QUESTION: 76

Due to limitations in data center power at the primary site, an asymmetrical VxRail Stretched Cluster has been deployed. Site 1 contains 12 hosts, Site 2 contains 16 hosts, and the Witness Host is in the third site. The administrator has configured affinity rules to run the heavier workloads in Site 2.

What vSAN storage policy settings should be used to ensure adequate workload distribution and data redundancy between sites?

A. Dual site mirroring (stretched cluster)

2 failures - RAID-1 (Mirroring)

B. None - stretched cluster

No Data Redundancy

- C. None - keep data on Non-Preferred (stretched cluster)
1 failure - RAID-1 (Mirroring)
- D. None - keep data on Non-Preferred (stretched cluster)
No Data Redundancy

Answer: C ([LEAVE A REPLY](#))

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)

NEW QUESTION: 77

What is a requirement for Top of Rack (ToR) switch VxRail node ports?

- A. Disable Link Aggregation
- B. Disable IGMP Snooping
- C. Enable Spanning Tree
- D. Enable IGMP Querier

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 78

Which mode must be enabled to support multiple VLANs on ToR ports?

- A. Access
- B. Trunk
- C. Link Aggregation
- D. Port-Channel

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 79

How long is the grace period for the vSphere evaluation licenses in a new VxRail implementation?

- A. 30 days
- B. 60 days
- C. 90 days
- D. 45 days

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 80

Which VxRail model requires iDRAC to be configured to LOM1?

- A. D
- B. V
- C. G
- D. S

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 81

Which vSAN setting is enabled by default during the initial deployment of a VxRail cluster?

- A. Deduplication and Compression
- B. Performance Service
- C. Storage policy of FTT = 1
- D. Encryption

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 82

Which VxRail node type support only hybrid storage?

- A. E Series
- B. V Series
- C. G Series
- D. S Series

Answer: ([SHOW ANSWER](#)**)**

NEW QUESTION: 83

How does an implementer get a local VxRail Configuration XML file so they can generate an As-Built Configuration Report?

- A. Open an FTP connection to the VxRail Manager VM with the mystic user Go to the /var/lib/vmware-marvin directory GET the config-initial.json file
- B. SSH to the VxRail Manager VM with the mystic user
SU to root
Go to the /opt/VxRail/config directory
SCP the initial-config.json file to a local location
- C. Log in to vCenter with the vSphere Client with the vCenter Administration user Go to Configure > VxRail > System Use the Product Documentation option
- D. Log in to vCenter with the vSphere Client with the vCenter Server Management user Go to Monitor > VxRail > Last Configuration Data Sent Use the Download option

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 84

Where can the latest VxRail Pre-Installation Site Checklist be obtained for a new deployment?

- A. Service offering index

- B. EMC Support VxRail
- C. SolVe
- D. VxRail Master Knowledge Base article

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 85

What accurately describes the positioning of a VxRail?

- A. Converged architecture with enterprise grade resiliency
- B. Can start small and grow with a low entry cost
- C. Software defined solution with rack scale and integrated networking
- D. Can start small and grow to hundreds of nodes

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 86

What are the minimum requirements for a customer-supplied VDS in a VxRail deployment?

- A. 4 uplinks
Port groups for Discovery, Management, vMotion, and vSAN only
- B. 2 uplinks
Port groups for Discovery, Management, vCenter Server, vMotion, and vSAN
- C. 2 uplinks
Port groups for Discovery, Management, vMotion, and vSAN
- D. 4 uplinks
Port groups for Discovery, Management, vCenter Server, vMotion, and vSAN

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 87

Which VxRail Series is designed to support a VDI environment and requires a GPU card in each host?

- A. G Series
- B. V Series
- C. S Series
- D. P Series

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 88

Which software component is an optional add-on for VxRail?

- A. VMware vRealize Operations
- B. VMware vSAN
- C. Dell EMC Secure Remote Support
- D. VMware vRealize Log Insight

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 89

In a VxRail internal vCenter deployment, which component(s) are automatically licensed?

- A. vCenter only
- B. vCenter and vSAN
- C. None
- D. vSAN only

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 90

An implementation engineer places a VxRail node into maintenance mode using the Ensure accessibility setting.

What is the engineer likely planning to do?

- A. Extensive maintenance
- B. Temporary maintenance
- C. Shutdown of an entire cluster
- D. Permanent removal of host from cluster

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 91

A new enterprise customer will be deploying VxRail, utilizing an existing vCenter.

Which server will be used to add and validate the host and domain names?

- A. Internal DNS server on VxRail Manager
- B. Customer external vCenter with host file
- C. Customer external DNS server
- D. Internal DNS server deployed on node1

Answer: ([SHOW ANSWER](#))

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)

NEW QUESTION: 92

Which network feature is unsupported on the VxRail system NIC ports?

- A. Link aggregation
- B. Multicast

C. Spanning Tree

D. Unicast

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 93

Which VxRail configurations can be reviewed using the As-Built Configuration Report at the time the report is generated?

A. Node names, vSAN interface IP addresses, and VxRail Manager users and passwords

B. Node PSNT numbers, license activation dates, and Private Management Network VLAN ID

C. Node models, license keys, vSAN VLAN ID, and vMotion VLAN ID

D. vMotion interface IP addresses, vCenter users and passwords, and opened firewall ports

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 94

An implementation engineer has just completed the deployment of a new VxRail cluster. They are unable to connect to the vCenter Server.

What can they use to confirm the physical health of the VxRail nodes?

A. iDRAC

B. vSphere Client

C. VxRail Manager

D. SRS

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 95

What is the benefit of using WTS in a VxRail Stretched Cluster implementation?

A. Separation of witness traffic from vSAN data traffic

B. Service automatically updates the witness appliance

C. Native implementation of terminal services in a VxRail

D. Access to Windows Terminal Services acceleration module

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 96

An implementation engineer is validating a VxRail deployment of six V570F nodes, each with four 10 Gb connections. The VxRail nodes have not been powered on.

Which command should they run to confirm that the Dell EMC ToR switch is configured correctly?

A. show lldp neighbors

B. show interface status

C. show port-channel summary

D. show running-config

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 97

Which two log files can be used for troubleshooting when deploying a new VxRail Cluster?

- A. marvin.log and dayone.log
- B. localhost_access_log.txt and dayone.log
- C. loudmouth.log and short.term.log
- D. loudmouth.log and dayone.log

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 98

A VxRail 7.0.100 environment is managed by the internal vCenter Server. The customer asks the implementation engineer to deploy a new VxRail cluster using the existing vCenter Server. What should the response of the engineer?

- A. Not supported on VxRail software 7.0.100
- B. Only supported on VxRail software 4.7.xxx
- C. Supported by neither the internal vCenter Server nor external vCenter Server
- D. Not supported for internal vCenter Server

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 99

According to Dell best practices, which VxRail series can be deployed in either datacenters or remote locations?

- A. D Series
- B. G Series
- C. E Series
- D. V Series

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 100

What is a requirement for the Top of Rack (ToR) switches used in a VxRail implementation?

- A. IPV4 and IPV6 Multicast
- B. LACP
- C. EtherChannel
- D. MLD Querier

Answer: A ([LEAVE A REPLY](#))

NEW QUESTION: 101

What is the VxRail maximum cluster size if using 10 GbE links?

- A. 16
- B. 64 with an RPQ
- C. 8
- D. 32 with an RPQ

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 102

What is a consideration when using ToR switches with VxRail?

- A. VxRail iDRAC Management ports require 10 GbE ports.
- B. IPv6 Multicast must be disabled in this environment.
- C. Link aggregation must be enabled on VxRail switch ports.
- D. All-Flash models must use 10 GbE or faster ports.

Answer: D ([LEAVE A REPLY](#))

NEW QUESTION: 103

You need to create a VxRail JSON file to generate a VxRail As-Built configuration report. How should you obtain this file?

- A. Download it from the vSphere client VxRail plug-in - Last Configuration Data Sent
- B. Download it from the VxRail First Run Wizard after a successful validation
- C. Generate it from the VxRail PEQ by clicking the Generate Appliance JSON button
- D. Generate it from the VxRail PEQ by clicking the Generate NVT/FDC JSON button

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 104

In which three VxRail Configuration Portal locations can an implementation engineer download the cluster configuration file? (Select 3)

- A. From the My Clusters Tab in the VxRail Configuration Portal
- B. From the Resources tab in the Edit Cluster Configuration wizard
- C. From the Validate Configuration File tab when editing a cluster
- D. From the My Deployments tab in the VxRail Configuration Portal
- E. From the customer Dell Digital Locker website

Answer: A,C,D ([LEAVE A REPLY](#))

NEW QUESTION: 105

You are in the validation phase of a VxRail deployment with two Top of Rack (ToR) switches and four V570F VxRail nodes.

Which command should you issue on each of the ToR switches to validate that Link Aggregation has not been configured for VxRail interfaces?

- A. show running config mld
- B. show spanning tree
- C. show interfaces port-channel brief
- D. show vlan

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 106

What is a requirement for Top-of-Rack (ToR) switches when deploying a VxRail cluster?

- A. Must have two switches in the cluster
- B. Must support 25GbE connectivity
- C. Must be manufactured by Dell, Cisco, or Brocade
- D. Must support IPv6 Multicast

Answer: D ([LEAVE A REPLY](#))

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)

NEW QUESTION: 107

A local upgrade is planned for a VxRail 7.0.xxx cluster.

For which Service VMs are snapshots recommended prior to the upgrade?

- A. VxRail Manager
VMware Log Insight
- B. VMware vCenter Appliance
VxRail Manager
- C. VMware vCenter Appliance
VMware vRealize Operations
- D. VMware vCenter Appliance
VMware vCenter Server PSC

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 108

What is the maximum number of nodes in a VxRail cluster when using 1 GbE links?

- A. 4
- B. 16
- C. 32
- D. 8

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 109

What is a consideration when performing a VxRail software upgrade from version 4.7.xxx to version 7.0.xxx?

- A. VxRail Manager VM must be changed to the default name to avoid an upgrade failure

- B. vCenter Server requires a temporary IP address on a different subnet before the upgrade
- C. Secure boot must be enabled on the ESXi hosts for a successful upgrade
- D. External vCenter server must be upgraded after the VxRail is upgraded

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 110

What is the name of the default port group with VLAN ID 3939 on an unconfigured VxRail node?

- A. Private Discovery Network
- B. Discovery Network
- C. Private Management Network
- D. Management Network

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 111

Which requirement must be met when expanding a 3-node VxRail G560F cluster with a fourth G Series node in the same chassis?

- A. PCIe network card must be added to all nodes
- B. New node must be at the same VxRail version as existing nodes
- C. Node requires only the same drive configuration
- D. Node hardware must be identical to the other three nodes

Answer: B ([LEAVE A REPLY](#))

NEW QUESTION: 112

What is the base URL for the VxRail API call?

- A. http://<VxM_IP>/vxm/v1/
- B. https://<VCenter_IP>/rest/vxm/v1/
- C. https://<VxM_IP>/rest/vxm/v1/
- D. https://<VxM_IP>/API/vxm/v1/

Answer: C ([LEAVE A REPLY](#))

NEW QUESTION: 113

An implementation engineer is attempting to add a new node to a 3 node VxRail cluster.

What is the minimum VxRail code version that no longer requires the fourth node to match the first three nodes?

- A. 4.0.302
- B. 4.5.150
- C. 4.5.070
- D. 4.0.502

Answer: ([SHOW ANSWER](#))

NEW QUESTION: 114

When preparing to generate an As-Built Configuration Report, it is determined that the VxRail Configuration JSON file was not saved from the Deployment Wizard.

What actions must be taken to retrieve the JSON file?

- A. SSH to the VxRail Manager VM with the mystic user SU to root Go to the /opt/VxRail/config directory SCP the initial-config json file to a local location
- B. Log in to vCenter with the vSphere Client with the vCenter Administration user Go to Configure > VxRail > System Use the Product Documentation option
- C. Open an FTP connection to the VxRail Manager VM with the mystic user Go to the /var/lib/vmware-marvin directory GET the config-initial json file
- D. Log in to vCenter with the vSphere Client with the vCenter Server Management user Go to Monitor > VxRail > Last Configuration Data Sent Use the Download option

Answer: D (LEAVE A REPLY)

NEW QUESTION: 115

Where can an administrator find steps to perform a manual verification of the customer network?

- A. Pre-Engagement Questionnaire (PEQ)
- B. Dell Technologies SolVe Online
- C. Dell EMC VxRail Network Planning Guide
- D. Customer Simplified Form

Answer: (SHOW ANSWER)

NEW QUESTION: 116

For which VxRail models must the iDRAC NIC Selection be set to Dedicated?

- A. E, P, S, and V Series only
- B. D, E, and G Series
- C. D, G, P, S, and V Series
- D. D, E, P, S, and V Series

Answer: (SHOW ANSWER)

Valid D-VXR-DY-23 Dumps shared by Actual4test.com for Helping Passing D-VXR-DY-23 Exam! Actual4test.com now offer the **newest D-VXR-DY-23 exam dumps**, the Actual4test.com D-VXR-DY-23 exam **questions have been updated** and **answers have been corrected** get the **newest** Actual4test.com D-VXR-DY-23 dumps with Test Engine here: https://www.actual4test.com/D-VXR-DY-23_examcollection.html (375 Q&As Dumps, **30%OFF** Special Discount: **Freepdfdumps**)